



Angela Comstock <deputycityclerk@stacymn.org>

---

## Fwd: Estimate 1675 from LJ Construction

2 messages

---

**Aerica Benson** <stacysportsgrill@stacymn.org>

Wed, Oct 4, 2023 at 2:31 PM

To: Angela Comstock <deputycityclerk@stacymn.org>, Michelle Hayes <michellehayes@stacymn.org>

1 of 2 concrete bids for the council packet. The other should be coming to me sometime tonight - I'll send it over as soon as I see it.

Thanks!

----- Forwarded message -----

From: **LJ Concrete** <quickbooks@notification.intuit.com>

Date: Tue, Oct 3, 2023 at 6:03 AM

Subject: Estimate 1675 from LJ Construction

To: <stacysportsgrill@stacymn.org>

Dear Aerica,

Please review the estimate below. Feel free to contact us if you have any questions. We look forward to working with you.

Thanks for your business!  
LJ Construction

----- Estimate Summary -----

Estimate # : 1675

Estimate Date: 09/25/2023

Total: \$6,440.00

The complete version has been provided as an attachment to this email.

-----



**Estimate\_1675\_from\_LJ\_Concrete.pdf**

22K

---

**Angela Comstock** <deputycityclerk@stacymn.org>

Wed, Oct 4, 2023 at 5:24 PM

To: Aerica Benson <stacysportsgrill@stacymn.org>

Cc: Michelle Hayes <michellehayes@stacymn.org>

Got it, thank you!

Angie Comstock  
Deputy City Clerk  
30955 Forest Blvd.  
Stacy, MN 55079  
651-462-4486

[Quoted text hidden]



**LJ Concrete**  
 55 6th St NW  
 Forest Lake, MN  
 55025 US  
 6513197047  
 ljconstruction15@gmail  
 .com



**ADDRESS**

Aerica  
 6007 Stacy Trail  
 Stacy, MN 55079

**Estimate 1675**

**DATE 09/25/2023**

DATE	ACTIVITY	DESCRIPTION	QTY	RATE	AMOUNT
	<b>04 Concrete</b>	Front sidewalk.  370 sqft Tear out and dispose of existing concrete. Base and compact. 4" thick. #3 rebar throughout. Expansion where needed. Standard gray concrete. Broom finish. Apply sealer. Does not include the stoop pad that sits on foundation.	370	12.00	4,440.00
	<b>04 Concrete</b>	Install new truncated domes.  5 domes. I would advise checking with city to see if this is needed.	5	400.00	2,000.00

**TOTAL \$6,440.00**

Accepted By

Accepted Date



Angela Comstock <deputycityclerk@stacymn.org>

**Fwd: Estimate 1688 from J&B Concrete**

1 message

**Aerica Benson** <stacysportsgrill@stacymn.org>

Wed, Oct 4, 2023 at 8:16 PM

To: Angela Comstock <deputycityclerk@stacymn.org>, Michelle Hayes <michellehayes@stacymn.org>

2nd and final concrete bid for the council packet.

Thanks!

----- Forwarded message -----

From: **J&B Concrete** <quickbooks@notification.intuit.com>

Date: Wed, Oct 4, 2023 at 8:13 PM

Subject: Estimate 1688 from J&B Concrete

To: <Stacysportsgrill@stacymn.org>

Please review the estimate below. Feel free to contact us if you have any questions.  
We look forward to working with you.

Thanks for your business!  
J&B Concrete

----- Estimate -----

2748 221st Ave NE  
East Bethel, MN 55011 US  
6122206688

Estimate #: 1688  
Date: 10/04/2023  
\$6,400.00

-----  
Address:

Aerica  
Stacy Bar  
6007 Stacy Trail  
Stacy, MN 55079

Date	Activity	Description	Amount
10/04/2023	Sidewalk	R-Remove sidewalk in front entry way and haul off site -Final grade to 4" depth and compact thoroughly -Pour new sidewalk to be broom finished -Install two new truncated domes to replace existing -Seal sidewalk with TK AS1 Acro Seal sealer	6,400.00T

-----  
SubTotal: \$6,400.00

Tax: \$0.00

-----  
Total: \$6,400.00

Dear Aericia,

Please review the estimate above. Feel free to contact us if you have any questions.

We look forward to working with you.

Jesse Bertilson  
J&B Concrete  
(612) 220-6688

Thank you for your business!



**Estimate\_1688\_from\_JB\_Concrete.pdf**

73K

**J&B Concrete**

2748 221st Ave NE  
East Bethel, MN 55011 US  
jbconcretejesse@gmail.com



**Estimate**

ADDRESS

Aerica  
Stacy Bar  
6007 Stacy Trail  
Stacy, MN 55079

SHIP TO

Aerica  
Stacy Bar  
6007 Stacy Trail  
Stacy, MN 55079

ESTIMATE

1688

DATE

10/04/2023

DATE	ACTIVITY	DESCRIPTION	AMOUNT
	Sidewalk Repair	-Remove sidewalk in front entry way and haul off site -Final grade to 4" depth and compact thoroughly -Pour new sidewalk to be broom finished -Install two new truncated domes to replace existing -Seal sidewalk with TKAS1 Acro Seal sealer	6,400.00

Dear Aerica,

Please review the estimate above. Feel free to contact us if you have any questions.  
We look forward to working with you.

Jesse Bertilson  
J&B Concrete  
(612) 220-6688

Thank you for your business!

SUBTOTAL	6,400.00
TAX	0.00
<b>TOTAL</b>	<b>\$6,400.00</b>

Accepted By

Accepted Date